

GPS #: **R147**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 710/C-3

City / Location: Unin., Orange County

Scale Factor: 1.00001120

Ellipsoid Red. Factor: 0.99994004

Combination Factor: 0.99995124

Convergence Angle: -00 51 23.81203

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 48.12776	117 48 31.85331	2291642.639	6088898.650	1254.489
2007.00	33 56 48.14427	117 48 31.87011	2291644.33	6088897.26	

References: RS 92-1117

Description:

FD 2" I.P. WITH BRASS CAP STAMPED "R9W, T2S, SEC. 34, 1/4, 1/4, SEC. 3, T2S, R9W", UP 1.0'. WITNESS PIPE 2 1/2' NORTH AND WITNESS PADDLE 3' NORTH. LOCATED NE OF THE INTER OF VALENCIA AVE. AND LAMBERT RD.; SET ON THE COUNTY LINE ALONG A RIDGE, EAST OF OLINDA LANDFILL.

