

GPS #: **R150**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 710/F-3

City / Location: Unin., Orange County

Scale Factor: 1.00001110

Ellipsoid Red. Factor: 0.99996504

Combination Factor: 0.99997617

Convergence Angle: -00 50 33.17972

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 46.53920	117 46 59.71374	2291366.972	6096657.980	731.967
2007.00	33 56 46.55569	117 46 59.73042	2291368.66	6096656.60	

References: RS 92-1117, CR 1996-0313

Description:

FD 2" I.P. WITH BRASS CAP STAMPED "LA CO., T2S, R9W, 35, 36, 2, 1, T3S, R9W, O.CO.", UP 0.8'. WITNESS PIPE 2' NORTH AND WITNESS PADDLE 3' NORTH. LOCATED NW OF THE INTER OF CARBON CANYON RD. AND THE ORANGE COUNTY/ SAN BERNARDINO COUNTY LINE; SET SW OF A TRAILER INSIDE THE ENTRANCE OF THE "CITY OF GOD - HILL OF HOPE CHURCH", NEAR AN ANGLE POINT IN FENCE.

