

GPS #: **R151**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 710/F-3

City / Location: Unin., Orange County

Scale Factor: 1.00001110

Ellipsoid Red. Factor: 0.99996548

Combination Factor: 0.99997660

Convergence Angle: -00 50 32.82032

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 56 46.53786	117 46 59.05973	2291366.027	6096713.072	722.787
2007.00	33 56 46.55440	117 46 59.07643	2291367.72	6096711.69	

References: RS 92-1117, CR 1996-0313

Description:

FD 1" I.P. TAGGED LS 3069, DOWN 0.5', PER SAN BERNARDINO COUNTY R/S 68/18-19. LOCATED NW OF THE INTER OF CARBON CANYON RD. AND THE ORANGE COUNTY/ SAN BERNARDINO COUNTY LINE; SET APPROX. 20' SE ALONG THE FENCE FROM THE GATE TO THE "CITY OF GOD - HILL OF HOPE CHURCH", AND 1.5' SW OF THE FENCE.

