

GPS #: **R153**

Date Destroyed: **7/25/2000**

Date Revised:

Benchmark Designation:

OCS Index Map: **3L**

Page/Grid: **767/A-5**

City / Location: **Lakewood, Los Angeles Co.**

Scale Factor: **0.99999225**

Ellipsoid Red. Factor: **1.00000360**

Combination Factor: **0.99999589**

Convergence Angle: **-00 59 42.43117**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 50 05.48172	118 03 39.22945	2252181.885	6011757.429	-74.741
2007.00	33 50 05.49773	118 03 39.24733	2252183.53	6011755.95	

References: **RS 92-1117**

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PK NAIL AND 1 1/2" OCS BRASS TAG STAMPED "GPS 153", FLUSH IN ASPHALT. LOCATED NORTH OF LINCOLN AVE. AND COYOTE CREEK; AROUND THE CONFLUENCE OF COYOTE CREEK AND MOODY CREEK.