

GPS #: **R167**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 796/G-7

City / Location: Seal Beach

Scale Factor: 0.99998280

Ellipsoid Red. Factor: 1.00000520

Combination Factor: 0.99998802

Convergence Angle: -01 00 47.35291

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 06.00744	118 05 37.37260	2228153.360	6001364.836	-107.982
2007.00	33 46 06.02380	118 05 37.38985	2228155.04	6001363.41	

References: RS 92-1117

Description:

FD 2 1/2" BRASS LA COUNTY ENGINEER DISK
STAMPED "STA 4 NOV. 92 RE 11915", DOWN 0.3'.
LOCATED NORTH OF THE INTER OF WESTMINSTER
AVE. AND THE LOS ALAMITOS CHANNEL; SET NEAR
ANGLE POINT ON THE WEST SIDE OF THE LEVEE.

