

GPS #: **R168**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 796/F-7

City / Location: Seal Beach

Scale Factor: 0.99998348

Ellipsoid Red. Factor: 1.00000510

Combination Factor: 0.99998867

Convergence Angle: -01 00 53.62625

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 24.53307	118 05 48.78870	2230042.745	6000434.402	-107.244
2007.00	33 46 24.54938	118 05 48.80590	2230044.42	6000432.98	

References: RS 92-1117

Description:

FD 2 1/2" BRASS DISK STAMPED "COUNTY ENGINEER RE 11915 STA.5 NOV. 1992 L.A.CO.OR.CO.", SET IN 6" DIA. CONC. POST, DOWN 0.7'. LOCATED NW OF THE INTER OF THE LOS ALAMITOS CHANNEL AND WESTMINSTER AVE.; SET APPROX. 80' SE OF THE E'LY LEVEE OF THE SAN GABRIEL RIVER.

