

**GPS #:** **R172**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 767/D-1

City / Location: Cerritos

Scale Factor: 0.99999715

Ellipsoid Red. Factor: 1.00000320

Combination Factor: 1.00000030

Convergence Angle: -00 58 56.39253

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 51 57.62765 | 118 02 15.44934 | 2263394.571   | 6019018.092  | -66.076               |
| 2007.00          | 33 51 57.64360 | 118 02 15.46749 | 2263396.21    | 6019016.59   |                       |

References: RS 92-1117

**Description:**

FD COUNTY ENGINEER WELL MONUMENT WITH 2 1/2" BRASS CAP STAMPED "COUNTY ENGINEER RE 11915 STA.23 NOV.92 LA.CO. OR. CO.", DOWN 0.6'. LOCATED AT THE APPARENT CENTERLINE INTER OF 183RD ST. AND MARQUARDT AVE.

