

**GPS #:** **R532**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 772/E-7

City / Location: Unin., Orange County

Scale Factor: 0.99998932

Ellipsoid Red. Factor: 0.99989884

Combination Factor: 0.99988816

Convergence Angle: -00 45 51.30987

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 54.66755	117 38 26.77319	2243065.520	6139231.765	2115.967
2007.00	33 48 54.68408	117 38 26.78964	2243067.21	6139230.40	

References: RS 92-1119

**Description:**

"NE COR, SEC 19, T4S, R7W" - FD SLATE STONE 0.8' X 0.5' X 0.5' HIGH WITH 1 3/8" O.C.S. BRASS TAG STAMPED "6/84" IN EPOXY. LOCATED FROM THE INTER OF BLACK STAR CANYON RD. AND SILVERADO CANYON RD., PROCEED N'LY ALONG BLACK STAR CANYON RD. 1.1 MILES TO A LOCKED IRON GATE (U.S. FOREST KEY), PROCEED THRU GATE ALONG SAID RD. 0.5 MILE TO A SHARP RIGHT TURN INTO BLACK STAR CANYON, CONTINUE RIGHT AND E'LY ALONG SAID RD. 5.25 MILES. HIKE 4000'+/- NE'LY ALONG THE CREEK BED TO SAID STATION LOCATED ON SIDE OF HILL, IN CLEVELAND NATIONAL

