

GPS #: **R537**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 802/D-2

City / Location: Unin., Orange County

Scale Factor: 0.99998727

Ellipsoid Red. Factor: 0.99990555

Combination Factor: 0.99989282

Convergence Angle: -00 46 07.73877

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 03.55492	117 38 56.67013	2237933.066	6136640.104	1975.639
2007.00	33 48 03.57139	117 38 56.68645	2237934.75	6136638.75	

References: RS 92-1119

Description:

"S 1/4, SEC 19, T4S, R7W" - FD 2" I.P. WITH 1 1/4" ALUMINUM TAG STAMPED "LS 2348 S19 S30 1/4 BONE" DOWN 0.2' WITH A WITNESS PADDLE 1' W'LY - LOCATED FROM THE INTER OF BLACK STAR CANYON RD. AND SILVERADO CANYON RD., PROCEED N'LY ALONG BLACK STAR CANYON RD. 1.1 MILES TO A LOCKED IRON GATE (U.S. FOREST KEY), PROCEED THRU GATE ALONG SAID RD. 0.5 MILE TO A SHARP RIGHT TURN INTO BLACK STAR CANYON, CONTINUE RIGHT AND E'LY ALONG SAID RD. 5.25 MILES TO "HIDDEN RANCH" LOCKED GATE (DA1 KEY) ON RIGHT. GO THRU GATE AND FOLLOW FAINT RD. SOUTH OF HOUSE AND UP STEEP HILL, THEN NE'LY 0.4 MILE AND STOP. HIKE S'LY 300'+/- UNTIL YOU REACH A GULLY, PROCEED DOWN CENTER OF GULLY SW'LY 300'+/- TO SAID STATION LOCATED IN GULLY, IN THE CLEVELAND NATIONAL FOREST.

