

GPS #: **R538**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 802/A-4

City / Location: Unin., Orange County

Scale Factor: 0.99998538

Ellipsoid Red. Factor: 0.99994862

Combination Factor: 0.99993401

Convergence Angle: -00 46 44.85757

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 15.02256	117 40 04.21812	2233104.696	6130873.611	1075.513
2007.00	33 47 15.03902	117 40 04.23429	2233106.38	6130872.27	

References: RS 92-1119

Description:

"NW COR LOT 1, SEC 36, T4S, R8W" - FD 1" I.P. WITH 1 1/2" O.C.S. BRASS TAG STAMPED "R.E. 561" UP 0.2' - LOCATED FROM THE INTER OF BLACK STAR CANYON RD. AND SILVERADO CANYON RD., PROCEED N'LY ALONG BLACK STAR CANYON RD. 1.1 MILES TO A LOCKED IRON GATE (U.S. FOREST KEY), PROCEED THRU GATE ALONG SAID RD. 0.5 MILE TO A SHARP RIGHT TURN INTO BLACK STAR CANYON, CONTINUE RIGHT AND E'LY ALONG SAID RD. 1.8 MILES TO JUST ACROSS THE THIRD BRIDGE, TO A SHARP RIGHT TURN WITH A PIPE GATE TO TUTTLE'S PROPERTY ON LEFT. TAKE LEFT THRU GATE (MUST HAVE PERMISSION FROM TUTTLE FAMILY) AND CONTINUE W'LY 0.2 MILE PAST TRAILER TO A SHARP RIGHT TURN UPHILL, N'LY, AND CONTINUE 0.1 MILE TO GRADED PAD AND PARK. HIKE W'LY 600'+/- ACROSS FIRST GULLY AND CONTINUE TO SECOND GULLY, SAID STATION IS LOCATED ON W'LY SIDE OF GULLY ALONG WIRE FENCE.

