

GPS #: **R539**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 802/B-4

City / Location: Unin., Orange County

Scale Factor: 0.99998538

Ellipsoid Red. Factor: 0.99994983

Combination Factor: 0.99993522

Convergence Angle: -00 46 41.96723

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 15.01240	117 39 58.95833	2233097.636	6131317.493	1050.169
2007.00	33 47 15.02887	117 39 58.97452	2233099.32	6131316.15	

References: RS 92-1119

Description:

"NE COR LOT 1, SEC 36, T4S, R8W" - FD 1 1/2" I.P. WITH WOOD PLUG AND 3/4" BRASS TAG STAMPED "RCE 21784" UP 0.1' WITH WITNESS PADDLE 1' S'LY - LOCATED FROM THE INTER OF BLACK STAR CANYON RD. AND SILVERADO CANYON RD., PROCEED N'LY ALONG BLACK STAR CANYON RD. 1.1 MILES TO A LOCKED IRON GATE (U.S. FOREST KEY), PROCEED THRU GATE ALONG SAID RD. 0.5 MILE TO A SHARP RIGHT TURN INTO BLACK STAR CANYON, CONTINUE RIGHT AND E'LY ALONG SAID RD. 1.8 MILES TO JUST ACROSS THE THIRD BRIDGE, TO A SHARP RIGHT TURN WITH A PIPE GATE TO TUTTLE'S PROPERTY ON LEFT. TAKE LEFT THRU GATE (MUST HAVE PERMISSION FROM TUTTLE FAMILY) AND CONTINUE W'LY 0.2 MILE PAST TRAILER TO A SHARP RIGHT TURN UPHILL, N'LY, AND CONTINUE 0.1 MILE TO GRADED PAD AND PARK. HIKE W'LY UPHILL 200'+/- N'LY TO SAID STATION LOCATED ON SIDE OF HILL.

