

**GPS #:** **R542**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 802/D-4

City / Location: Unin., Orange County

Scale Factor: 0.99998527

Ellipsoid Red. Factor: 0.99990754

Combination Factor: 0.99989281

Convergence Angle: -00 46 08.87249

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 11.94181	117 38 58.73326	2232718.638	6136395.981	1933.969
2007.00	33 47 11.95836	117 38 58.74943	2232720.33	6136394.64	

References: RS 92-1119

**Description:**

"S 1/4 SEC 30, T4S, R7W" - FD 3 1/2" ALUMINUM U. S. DEPARTMENT OF AGRICULTURE & FOREST SERVICE CADASTRAL SURVEY CAP STAMPED "T4S R7W S30 1/4 S31 LS 5716 1989" UP 0.2' IN ROCK PILE WITH WITNESS PADDLE 1'+/- NORTH. TO REACH THE STATION FROM THE INTER OF SILVERADO CANYON RD. AND BLACKSTAR CANYON RD., PROCEED NORTH ALONG BLACKSTAR CANYON RD. 0.65 MILE TO BAKER CANYON RD. ON RIGHT "FLYING B RANCH". TURN RIGHT AND PROCEED 0.30 MILE TO A DIRT RD. ON LEFT WITH A LOCKED BARBED WIRE FENCE GATE (DA1 KEY). PROCEED THRU GATE, TAKE FIRST LEFT AND GO 0.30 MILE TO A CREEK BED. CROSS CREEK BED AND CONTINUE N'LY ON SAME RD. 1.15 MILES THRU A GATE TO A THREE-WAY FORK OF DIRT RD.S. TAKE THE FAINT RD. TO THE RIGHT THAT LEADS MOST N'LY, THAN E'LY AND CONTINUE ALONG SAID RD. 0.45 MILE WINDING UPHILL AND AROUND THE HILL TO A "T" INTER WITH A DIRT RD. LOCATED IN A SANDSTONE BOULDER FIELD AREA. TURN LEFT AND GO UP STEEP AND BUMPY HILL AND FOLLOW ALONG DIRT RD. ON TOP OF RIDGE FOR AS FAR AS YOU CAN GO. RD. GETS VERY ROCKY AND STEEP AT THE END. PARK AT THE END AND HIKE ALONG TRAIL N'LY

