

GPS #: R543

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 802/B-5

City / Location: Unin., Orange County

Scale Factor: 0.99998441

Ellipsoid Red. Factor: 0.99995508

Combination Factor: 0.99993949

Convergence Angle: -00 46 43.75983

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 49.32943	117 40 02.22048	2230505.500	6131006.899	940.605
2007.00	33 46 49.34586	117 40 02.23673	2230507.18	6131005.55	

References: RS 92-1119

Description:

"SW COR LOT 2, SEC 36, T4S, R8W" - FD 2" I.P. WITH O.C.S. TAG STAMPED "RE 561" UP 1.2' WITH A REFERENCE POINT BEING 5'+/- SE'LY ON TOP OF 10' HIGH BOULDER, REFERENCE POINT BEING A FD NAIL WITH 1 1/2" O.C.S. BRASS TAG STAMPED "RP RE 561" EPOXIED TO BOULDER - LOCATED FROM THE INTER OF BLACK STAR CANYON RD. AND SILVERADO CANYON RD., PROCEED N'LY ALONG BLACK STAR CANYON RD. 1.1 MILES TO A LOCKED IRON GATE (U.S. FOREST KEY), PROCEED THRU GATE ALONG SAID RD. 0.5 MILE TO A SHARP RIGHT TURN INTO BLACK STAR CANYON, CONTINUE RIGHT AND E'LY ALONG SAID RD. 1.1 MILES UNTIL YOU CROSS THE SECOND NARROW BRIDGE. PARK AND HIKE UPHILL E'LY 200'+/- UP RIDGE, THEN GO S'LY 100'+/- ACROSS GULLY TO A LARGE BOULDER. SAID STATION IS LOCATED ON THE N'LY SIDE OF SAID BOULDER.

