

**GPS #:** **R544**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 802/B-5

City / Location: Unin., Orange County

Scale Factor: 0.99998439

Ellipsoid Red. Factor: 0.99995112

Combination Factor: 0.99993552

Convergence Angle: -00 46 42.02192

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 48.92445	117 39 59.05787	2230460.940	6131273.271	1023.305
2007.00	33 46 48.94088	117 39 59.07415	2230462.62	6131271.92	

References: RS 92-1119

**Description:**

"SE COR LOT 2, SEC 36, T4S, R8W" - FD 1 1/4" AXLE WITH 3/4" O.C.S. BRASS TAG STAMPED "RCE 21784" TIED TO IT, UP 0.3' WITH A WITNESS POST 6.8'+/- E'LY - LOCATED FROM THE INTER OF BLACK STAR CANYON RD. AND SILVERADO CANYON RD., PROCEED N'LY ALONG BLACK STAR CANYON RD. 1.1 MILES TO A LOCKED IRON GATE (U.S. FOREST KEY), PROCEED THRU GATE ALONG SAID RD. 0.5 MILE TO A SHARP RIGHT TURN INTO BLACK STAR CANYON, CONTINUE RIGHT AND E'LY ALONG SAID RD. 1.1 MILES UNTIL YOU CROSS THE SECOND NARROW BRIDGE. PARK AND HIKE UPHILL E'LY 600'+/- UP RIDGE, SAID STATION IS LOCATED 40'+/- ON S'LY SIDE OF RIDGE.

