

**GPS #:** **R546**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 802/C-2

City / Location: Unin., Orange County

Scale Factor: 0.99998727

Ellipsoid Red. Factor: 0.99991041

Combination Factor: 0.99989769

Convergence Angle: -00 46 15.98986

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 03.56754	117 39 11.68530	2237951.369	6135373.122	1874.038
2007.00	33 48 03.58408	117 39 11.70159	2237953.06	6135371.77	

References: RS 92-1119

**Description:**

"SW 1/4, LOT 2, SEC 19, T4S, R7W" - FD 1 1/2" I.P. WITH 1 1/4" ALUMINUM TAG STAMPED "COR 3 LS 2348 BONE 1/16" UP 0.3' LOCATED FROM THE INTER OF BLACK STAR CANYON RD. AND SILVERADO CANYON RD., PROCEED N'LY ALONG BLACK STAR CANYON RD. 1.1 MILES TO A LOCKED IRON GATE (U.S. FOREST KEY), PROCEED THRU GATE ALONG SAID RD. 0.5 MILE TO A SHARP RIGHT TURN INTO BLACK STAR CANYON, CONTINUE RIGHT AND E'LY ALONG SAID RD. 5.25 MILES TO "HIDDEN RANCH" LOCKED GATE (DA1 KEY) ON RIGHT. GO THRU GATE AND FOLLOW FAINT RD. SOUTH OF HOUSE AND UP STEEP HILL AND STOP. HIKE S'LY 100'+/- THRU BRUSH ALONG PATH AND THEN 400'+/- W'LY TO SAID STATION LOCATED ALONG NOSE OF HILLSIDE, IN THE CLEVELAND NATIONAL FOREST.

