

**GPS #:** **R550**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 742/A-6

City / Location: Unin., Orange County

Scale Factor: 0.99999771

Ellipsoid Red. Factor: 0.99998421

Combination Factor: 0.99998192

Convergence Angle: -00 46 52.47328

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 52 10.03618	117 40 18.07701	2262939.187	6130110.610	331.397
2007.00	33 52 10.05274	117 40 18.09330	2262940.88	6130109.26	

References: RS 92-1119

**Description:**

FD PUNCHED SPIKE AND BRASS WASHER (ILLEGIBLE), FLUSH IN ASPHALT. LOCATED ALONG THE S'LY EDGE OF PAVEMENT OF THE EASTBOUND 91 FREEWAY BETWEEN COAL CANYON EXIT AND GREEN RIVER DR. EXIT, NEAR CALL BOX 91-188; SET AS AN APPARENT POINT- ON-LINE BETWEEN TRI-COUNTY CORNER (ORANGE, SAN BERNARDINO & RIVERSIDE) AND RV #1.

