

**GPS #:** **R556**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 742/A-6

City / Location: Unin., Orange County

Scale Factor: 0.99999763

Ellipsoid Red. Factor: 0.99998428

Combination Factor: 0.99998191

Convergence Angle: -00 46 54.69967

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 52 08.39495	117 40 22.12856	2262777.957	6129766.741	330.058
2007.00	33 52 08.41151	117 40 22.14486	2262779.65	6129765.39	

References: RS 92-1119

**Description:**

FD 4" X 4" CONC. POST WITH BRASS NAIL IN CENTER, UP 0.35'. LOCATED EAST OF THE INTER OF THE 91 FREEWAY AND COAL CANYON RD. EXIT; SET APPROX. 35' SOUTH OF THE SOUTH EDGE OF THE 91 FREEWAY, ON THE COUNTY LINE BETWEEN ORANGE AND RIVERSIDE COUNTIES.

