

GPS #: **R558**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 772/A-1

City / Location: Unin., Orange County

Scale Factor: 0.99999612

Ellipsoid Red. Factor: 0.99992996

Combination Factor: 0.99992609

Convergence Angle: -00 46 55.79046

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 34.54864	117 40 24.11354	2259359.180	6129552.672	1465.017
2007.00	33 51 34.56526	117 40 24.12997	2259360.88	6129551.31	

References: RS 92-1119

Description:

FD 2 1/2" I.P. WITH BRASS CAP STAMPED "T3S, R9W, S36, S1, T4S, 1990 LS CC, LS 5346", FLUSH. LOCATED IN A S'LY DIRECTION FROM THE INTER OF THE 91 FREEWAY AND COAL CANYON RD.; SET IN A STEEP RAVINE OFF A DIRT RD. (COAL CANYON SPUR)?, TO THE EAST OF SOME POWER LINES.

