

GPS #: **R561**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 803/C-6

City / Location: Unin., Orange County

Scale Factor: 0.99998262

Ellipsoid Red. Factor: 0.99982318

Combination Factor: 0.99980581

Convergence Angle: -00 43 47.29364

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 01.11902	117 34 41.09118	2225275.798	6158048.662	3696.682
2007.00	33 46 01.13578	117 34 41.10734	2225277.51	6158047.32	

References: RS 92-1119

Description:

FD 2" I.P. WITH 2 1/2" OCS BRASS DISK STAMPED "BEDFORD AUX. 11-1992", DOWN 0.1', WITH 8" CONC. COLLAR. LOCATED EAST OFF THE E'LY TERMINATION OF (ASPHALT) SILVERADO CANYON RD.; SET ON A RIDGE, AT THE COUNTY LINE. BETWEEN ORANGE/RIVERSIDE COUNTIES.

