

GPS #: **R562**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 833/H-1

City / Location: Unin., Orange County

Scale Factor: 0.99998121

Ellipsoid Red. Factor: 0.99981607

Combination Factor: 0.99979729

Convergence Angle: -00 42 24.28908

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



| Epoch Adjustment | Latitude | Longitude | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35 | 33 45 22.29235 | 117 32 10.04131 | 2221191.540 | 6170751.170 | 3845.465 |
| 2007.00 | 33 45 22.30929 | 117 32 10.05732 | 2221193.27 | 6170749.84 | |

References: RS 92-1119

Description:

FD 4" BRASS DISK SET IN CONC. ENCASED BY A 6" STOVEPIPE, STAMPED "BALD RESET 1949 COUNTY CORNER, A.C. KEITH RE 4388 W.K. HILLYARD RE 561 RIVERSIDE COUNTY, ORANGE COUNTY", PADDLE POST 1.5' EAST. LOCATED EAST OFF THE E'LY TERMINATION OF (ASPHALT) SILVERADO CANYON RD.; SET ON A RIDGE, AT THE COUNTY LINE BETWEEN ORANGE/RIVERSIDE COUNTIES.

