

**GPS #:** **R563**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 833/G-3

City / Location: Unin., Orange County

Scale Factor: 0.99997672

Ellipsoid Red. Factor: 0.99974167

Combination Factor: 0.99971840

Convergence Angle: -00 42 40.05650

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 10.56830	117 32 38.73451	2207907.629	6168163.467	5400.104
2007.00	33 43 10.58516	117 32 38.75024	2207909.35	6168162.16	

References: RS 92-1119

**Description:**

FD DETERIORATED 6" X 8" REDWOOD POST ENCASED BY CONC. AND ROCK COLLAR, BETWEEN 2 LARGE BOULDERS. SET 1" I.P. THROUGH CENTER OF REDWOOD POST WITH 2 1/2" OCS BRASS STAMPED "MODJESKA PEAK, 1992", WITH CONC. COLLAR ON TOP OF POST. LOCATED IN A SE'LY DIRECTION FROM THE E'LY TERMINATION OF (ASPHALT) SILVERADO CANYON RD.; SET ON A HILL EAST OF MAIN DIVIDE RD., KNOWN AS MODJESKA PEAK, AT THE COUNTY LINE BETWEEN ORANGE/RIVERSIDE COUNTIES.

