

**GPS #:** **R565**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 864/F-1

City / Location: Unin., Orange County

Scale Factor: 0.99997474

Ellipsoid Red. Factor: 0.99978486

Combination Factor: 0.99975961

Convergence Angle: -00 40 23.69412

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 42 08.16202 | 117 28 30.58525 | 2201346.751   | 6189048.451  | 4497.524              |
| 2007.00          | 33 42 08.17926 | 117 28 30.60090 | 2201348.51    | 6189047.15   |                       |

References: RS 92-1119

**Description:**

FD 6 1/2" CONC. POST WITH 4" BRASS DISK, STAMPED "RIVERSIDE COUNTY, AC KEITH, RE 4388, W HILLYARD, RE 561, ORANGE COUNTY, TRABUCO, COUNTY CORNER, RESET 1949, LS OCS RESET 1981", UP 0.3'. LOCATED IN AN E'LY DIRECTION FROM THE INTER OF ORTEGA HWY. AND THE 5 FREEWAY; SET OFF DIRT RD., UP A STEEP ROCKY RIDGE, NEAR TWO LONE PINE TREES, AT THE COUNTY LINE BETWEEN ORANGE/RIVERSIDE COUNTIES.

