

## HORIZONTAL CONTROL DATA SHEET CCS83, ZONE VI



**GPS #:** R566

**Date Destroyed:** 

Date Revised: 10/24/1996

**Benchmark Designation:** 

OCS Index Map: 6LC Page/Grid: 865/D-7

City / Location: Unin., Orange County


Scale Factor: 0.99997021

Ellipsoid Red. Factor: 0.99986243

Combination Factor: 0.99983265

Convergence Angle: -00 38 20.36437

Factors and Convergance Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 33.62863	117 24 46.15248	2185510.319	6207834.132	2876.576
2007.00	33 39 33.64570	117 24 46.16801	2185512.06	6207832.84	

References: RS 92-1119, CR 1401

## **Description:**

FD 4" I.P. WITH PUNCHED SPIKE AND OCS WASHER STAMPED "CO.COR.", UP 1.8'. LOCATED IN A E'LY DIRECTION FROM THE INTER OF ORTEGA HWY. AND THE 5 FREEWAY; SET ALONG EAST SIDE OF AN OLD FIRE BREAK CLEARING, AT THE COUNTY LINE BETWEEN ORANGE/RIVERSIDE COUNTIES.

