

GPS #: **R567**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 954/C-3

City / Location: Unin., Orange County

Scale Factor: 0.99996023

Ellipsoid Red. Factor: 0.99995022

Combination Factor: 0.99991046

Convergence Angle: -00 41 32.81436

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 03.35417	117 30 36.36874	2140344.689	6177683.623	1041.924
2007.00	33 32 03.37113	117 30 36.38451	2140346.42	6177682.31	

References: RS 92-1119

Description:

FD 2 1/2" I.P. WITH BRASS CAP STAMPED "RE 4231, RE 2839, R.M.V., C.C., S21, S28", UP 1.5'. LOCATED IN AN E'LY DIRECTION FROM THE INTER OF ORTEGA HWY. AND THE 5 FREEWAY; SET ON THE SOUTH FACE OF A GULLY, WEST OF A DIRT RD., AT THE COUNTY LINE BETWEEN ORANGE/RIVERSIDE COUNTIES.

