

GPS #: **R569**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 954/D-5

City / Location: Unin., Orange County

Scale Factor: 0.99995938

Ellipsoid Red. Factor: 0.99994916

Combination Factor: 0.99990855

Convergence Angle: -00 41 18.86523

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 11.03712	117 30 10.98442	2135031.153	6179768.638	1064.033
2007.00	33 31 11.05404	117 30 11.00012	2135032.88	6179767.33	

References: RS 92-1119

Description:

FD 2" I.P. WITH BRASS CAP STAMPED "T7S, R6W, S28, S33, S34, 1912", UP 1.65'. LOCATED IN A NE'LY DIRECTION FROM THE INTER OF ORTEGA HWY. AND THE 5 FREEWAY; SET OFF VERDUGO CANYON RD., AT THE COUNTY LINE BETWEEN ORANGE/RIVERSIDE COUNTIES.

