

GPS #: **R574**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 974/C-3

City / Location: Unin., Orange County

Scale Factor: 0.99995756

Ellipsoid Red. Factor: 0.99995434

Combination Factor: 0.99991190

Convergence Angle: -00 41 31.40087

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 29 02.51126	117 30 33.79652	2122064.499	6177680.561	955.887
2007.00	33 29 02.52822	117 30 33.81201	2122066.23	6177679.27	

References: RS 92-1120

Description:

FD 6" X 6" CONC. POST WITH 2 3/4" BRASS DISK STAMPED "U.S.N., CAMP JOSEPH H. PENDLETON BOUNDARY, INTER POINT, 1943", FLUSH. LOCATED IN AN E'LY DIRECTION FROM THE INTER OF ORTEGA HWY. AND THE 5 FREEWAY; SET ON A RIDGE OFF A DIRT RD., NORTH OF CAMP PENDELTON MARINE CORPS BASE, AT THE COUNTY LINE BETWEEN ORANGE/RIVERSIDE/SAN DIEGO COUNTIES.

