

**GPS #:** **R578**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 993/D-3

City / Location: Unin., Orange County

Scale Factor: 0.99995566

Ellipsoid Red. Factor: 0.99997462

Combination Factor: 0.99993028

Convergence Angle: -00 43 58.49459

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 26 02.85275	117 35 01.47443	2104188.910	6154778.726	532.076
2007.00	33 26 02.86970	117 35 01.48988	2104190.64	6154777.44	

References: RS 92-1120

**Description:**

FD 2" I.P. FILLED WITH CONC. AND 1/2" DIA. HOLE IN THE CENTER, 3" DEEP, UP 0.8'. LOCATED IN A N'LY DIRECTION FROM THE INTER OF THE 5 FREEWAY AND CRISTIANITOS RD.; SET WEST OF A BEND IN A S.C. EDISON DIRT RD., BY A FIRE BREAK, AT THE COUNTY LINE BETWEEN ORANGE AND SAN DIEGO COUNTIES.

