

**Designation: 1L-82-87**

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q04-14

Page/Grid: 741/G-6

City / Location: Yorba Linda

Line #/SSN: 403/0960

Established By: OCS 1987

Monument Type: Orange County Surveyor's 3 3/4"  
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
400.626	398.218	1987

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 52 26.86	117 41 46.46

**Description:**

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "1L-82-87", SET IN THE EASTERLY END OF A CONCRETE HEADWALL. MONUMENT IS LOCATED ALONG SOUTHERLY SIDE OF THE SANTA ANA RIVER SOUTHERLY LEVEE, 1.0 MILES EASTERLY ALONG THE ASPHALT BICYCLE TRAIL FROM THE CENTERLINE OF GYPSUM CANYON ROAD, 26 FT. SOUTHERLY OF THE CENTERLINE OF THE BIKE PATH, AND 0.5 FT. NORTHERLY OF A 5 FT. CHAINLINK FENCE. MONUMENT IS SET 5.0 FT. ABOVE THE BIKE PATH.

