

Designation: 3F-96-70

Date Destroyed:

Date Revised:

GPS #: 1505

OCS Index Map: Q16-08

Page/Grid: 921/A-3

City / Location: Laguna Beach

Line #/SSN: 356/0110

Established By: OCS 1970

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
268.245	265.893	1991

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 35 14.25657	117 45 17.92812

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3F-96-70", SET IN THE TOP OF A 6 IN. BY 6 IN. CONCRETE POST. MONUMENT IS LOCATED ALONG THE SOUTHEASTERLY SIDE OF EL TORO ROAD, 32.5 FT. SOUTHEASTERLY OF THE CENTERLINE OF EL TORO ROAD, 1 FT. NORTHWESTERLY OF A 3.5 FT. TALL BARBED WIRE FENCE, 6 FT. EASTERLY OF A STEEL WITNESS POST, 0.3 MILES SOUTHWESTERLY OF THE 73 TOLL ROAD OVERCROSSING OF EL TORO AND 95.5 FT. SOUTHWESTERLY OF POWER POLE #1502914E. MONUMENT IS SET 3 FT. BELOW ROAD LEVEL.

