

Designation: BLSA

Date Destroyed:

Date Revised: 8/6/2013

GPS #: BLSA

OCS Index Map: Q05-12

Page/Grid: 797/E-3

City / Location: Cypress

Line #/SSN:

Established By: Southern Calif. Integrated GPS Network

Monument Type: OCR TN



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
43.100	40.620	2005 adj
43.172	40.693	2002

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 47 58.342124	118 01 43.186539

Description:

THIS IS A CONTINUOUS GPS STATION (CGPS) AND IS PART OF THE CALIFORNIA SPATIAL REFERENCE NETWORK (CSR N). DATA IS RECORDED AT 30 SECOND EPOCHS, 24 HOURS A DAY, 7 DAYS A WEEK AND CAN BE DOWNLOADED FROM THE SCRIPPS WEB SITE @ [HTTP://SOPAC.UCSD.EDU](http://sopac.ucsd.edu). HORIZONTAL AND VERTICAL DATUM IS TO THE GEODETIC REFERENCE POINT (GRP). THE ANTENNA IS A TOPCON TPSCR.G3 (INSTALLED 06/09/2011). TRUE VERTICAL ANTENNA HEIGHT IS FROM THE GEODETIC REFERENCE POINT (GRP) TO THE BOTTOM OF THE ANTENNA PRE-AMP (BPA) AND IS 0.008 METERS (0.027 FEET).

