

Designation: CM-39-81

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q11-15

Page/Grid: 888/H-4

City / Location: Costa Mesa

Line #/SSN: 558/0090

Established By: OCS 1981

Monument Type: Orange County Surveyor's 3 3/4"
Aluminum Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
102.442	100.050	2005
102.508	100.101	1992

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 38 22.84	117 55 55.69

Description:

DESCRIBED BY OCS 2001 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "CM-39-81", SET IN THE SOUTHEAST CORNER OF A 3 FT. BY 15 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE SOUTHWEST CORNER OF THE INTERSECTION OF PLACENTIA AVENUE AND 18TH STREET, 23 FT. SOUTHERLY OF THE CENTERLINE OF 18TH STREET AND 0.5 FT. WESTERLY OF THE WEST END OF THE SOUTHWEST CURB RETURN. MONUMENT IS SET LEVEL WITH SIDEWALK.

