

Designation: E-785

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q20-07

Page/Grid: 972/A-6

City / Location: Dana Point

Line #/SSN: 402/0020

Established By: USC & GS 1946

Monument Type: Bronze / Brass Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
22.333	20.038	1989

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 28 02.72	117 40 47.31

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" USCGS BRONZED DISK STAMPED "E 785 1946", SET IN THE TOP OF A 6 IN. BY 6 IN. CONCRETE POST. MONUMENT IS LOCATED ALONG THE EASTERLY SIDE OF THE ATCHINSON/TOPEKA/SANTA FE RAILWAY, 0.3 MILES NORTHERLY ALONG THE RAILWAY FROM THE OVERCROSSING OF PACIFIC COAST HIGHWAY, 24.6 FT. NORTHERLY OF THE CENTERLINE OF A CONCRETE BOX CULVERT UNDERCROSSING, 5.2 FT. WESTERLY OF A CONCRETE CURB FOR A BOAT/RV PARKING FACILITY AND 15 FT. EASTERLY OF THE EASTERLY RAIL ALONG THE RAILWAY. MONUMENT IS SET 1 FT. LOWER THAN THE TRACKS.

