

**Designation: L-766**

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q10-01

Page/Grid: 826/F-4

City / Location: Seal Beach

Line #/SSN: 400/1190

Established By: USC & GS 1945

Monument Type: Bronze / Brass Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
12.977	10.488	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 44 35.15	118 06 01.07

**Description:**

DESCRIBED BY OCS 2002 - FOUND 3 3/4" US COAST AND GEODETIC SURVEY BRONZED DISK STAMPED "L 766 1945", SET IN THE TOP OF A BRICK WALL PILASTER. MONUMENT IS LOCATED IN THE WESTERLY CORNER OF THE INTERSECTION OF PACIFIC COAST HIGHWAY AND 12TH STREET, 52 FT. SOUTHWESTERLY OF THE CENTERLINE OF PCH AND 93 FT. NORTHWESTERLY OF THE CENTERLINE OF 12TH STREET. MONUMENT IS SET 4.0 FT. ABOVE THE SIDEWALK.

