

Designation: S-783

Date Destroyed:

Date Revised: 4/7/2004

GPS #:

OCS Index Map: Q20-06

Page/Grid: 971/J-6

City / Location: Dana Point

Line #/SSN: 400/0190

Established By: USC & GS 1946

Monument Type: Bronze / Brass Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
125.319	123.023	2004
125.298	123.002	1989

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 28 01.52	117 41 40.68

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" USCGS BRONZED DISK STAMPED "S-783", SET IN THE TOP OF A 6 IN. BY 6 IN. CONCRETE POST. MONUMENT IS LOCATED IN THE NORTHEASTERLY CORNER OF THE INTERSECTION OF NORTHBOUND PACIFIC COAST HIGHWAY AND ALCAZAR DRIVE, 21 FT. EASTERLY OF THE CENTERLINE OF ALCAZAR AND 39 FT. NORTHERLY OF THE CENTERLINE OF THE NORTHBOUND LANES OF PACIFIC COAST HIGHWAY. MONUMENT IS SET LEVEL WITH THE TOP OF THE CURB.

