

**Designation: T-779**

Date Destroyed:

Date Revised:

GPS #:

OCS Index Map: Q02-10

Page/Grid: 708/D-6

City / Location: La Habra

Line #/SSN: 401/0420

Established By: USC & GS 1946

Monument Type: Bronze / Brass Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
272.878	270.464	2005
272.933	270.521	1990

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 55 41.58	117 57 17.74

**Description:**

DESCRIBED BY OCS 2003 - FOUND 3 3/4" USCGS BRONZED DISK STAMPED "T 779 1946", SET IN THE TOP OF A CONCRETE POST. MONUMENT IS LOCATED IN THE NORTHWESTERLY CORNER OF THE INTERSECTION OF MONTE VISTA DRIVE AND A SINGLE SET OF RAILROAD TRACKS, 0.25 MILES SOUTHERLY ALONG MONTE VISTA FROM THE CENTERLINE OF LA HABRA BOULEVARD, 16 FT. NORTHERLY OF THE CENTERLINE OF THE RAILWAY, 25 FT. WESTERLY OF THE CENTERLINE OF MONTE VISTA AND 0.5 FT. WESTERLY OF THE EASTERLY EDGE OF THE SIDEWALK. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

