

**Designation: TIDAL-1**

Date Destroyed:  
 Date Revised: 6/27/2011  
 GPS #:  
 OCS Index Map: Q11-20  
 Page/Grid: 919/E-2  
 City / Location: Newport Beach  
  
 Line #/SSN: 406/0030  
 Established By: USC & GS 1926  
 Monument Type: Bronze / Brass Disk



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
10.190	7.854	2011
10.190	7.854	1994

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 35 49.64551	117 52 45.49398

**Description:**

RECOVERY NOTE BY OCS 2001 - FOUND 3 3/4" BRASS U.S. COAST AND GEODETIC SURVEY DISK STAMPED "No 1 1926" FLUSH IN SANDSTONE ROCK OUTCROPPING. MONUMENT IS LOCATED SOUTHWEST OF THE T-JUNCTION OF OCEAN BOULEVARD AND DAHLIA AVENUE, AT THE NEWPORT BAY ENTRANCE CHANNEL, 11.4 METERS (37.4 FT.) SOUTHWEST OF THE SOUTHWEST WALL OF THE WILLIAM O. KERKOFF LABORATORY, 8.1 METERS (26.6 FT.) NORTHWEST OF TIDAL BENCHMARK 2, 6.1 METERS (20 FT.) SOUTHEAST OF THE SOUTHEAST EDGE OF A SMALL PIER LEADING FROM THE WEST CORNER OF THE LAB TO THE WALL AROUND THE SOUTHWEST END OF THE LAB, THE STATION IS 2.4 METERS BELOW THE HEIGHT OF THE WALL.

