

Designation: V-282

Date Destroyed:

Date Revised:

GPS #: 1480

OCS Index Map: Q21-14

Page/Grid: 1023/C-3

City / Location: Unin., San Diego Co.

Line #/SSN: 400/0010

Established By: USC & GS 1955

Monument Type: Bronze / Brass Disk



| NAVD88 (ft) | NGVD29 (ft) | Year Leveled |
|-------------|-------------|--------------|
| 14.787 | 12.494 | 1988 |
| | | |
| | | |
| | | |
| | | |

| For Reconnaissance Only! | |
|--------------------------|---------------------|
| Latitude (30' +/-) | Longitude (30' +/-) |
| 33 23 10.19588 | 117 35 35.08016 |

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" USCGS BRONZED BENCHMARK DISK STAMPED "V-282", SET IN THE TOP OF A CONCRETE PIER FOR A STEEL BRIDGE FOR THE ATCHINSON TOPEKA SANTA FE RAILWAY OVER SAN MATEO CREEK. MONUMENT IS LOCATED ALONG THE SOUTHWESTERLY SIDE OF THE RAILWAY, FROM THE INTERSTATE 5 SOUTHBOUND OFF-RAMP AT CHRISTIANITOS ROAD PROCEED SOUTHERLY ACROSS CHRISTIANITOS TO AN ASPHALT SERVICE ROAD, 0.25 MILES SOUTHERLY ALONG ROAD TO AN INTERSECTION WITH A BRIDGE PROCEED RIGHT 0.4 MILES TO THE RAILWAY. PROCEED ON FOOT UNDER THE RAILWAY AND SOUTHERLY 500+/- FT. TO A SMALL PATH LEADING EASTERLY TO THE RAILWAY, THEN NORTHERLY ALONG RAILWAY 100+/- FT. AND 10.8 FT. SOUTHWESTERLY OF THE SOUTHWESTERLY RAIL. MONUMENT IS SET 5 FT. BELOW THE LEVEL OF THE TRACKS.

