

**Designation: WHYT**

Date Destroyed:

Date Revised: 11/9/2010

GPS #: WHYT

OCS Index Map: Q13-12

Page/Grid: 862/E-5

City / Location: Portola Hills

Line #/SSN:

Established By: Southern Calif. Integrated GPS Network

Monument Type: OCR TN



NAVD88 (ft)	NGVD29 (ft)	Year Leveled
984.403	982.039	2002

For Reconnaissance Only!	
Latitude (30' +/-)	Longitude (30' +/-)
33 40 28.152253	117 38 36.396318

**Description:**

THIS IS A CONTINUOUS GPS STATION (CGPS) AND IS PART OF THE ORANGE COUNTY REAL TIME NETWORK (OCR TN). FOR MORE INFORMATION, PLEASE VISIT:

[http://ocpublicworks.com/OCsurvey/Documents/pdf/Procedures\\_for\\_using\\_OCR TN.pdf](http://ocpublicworks.com/OCsurvey/Documents/pdf/Procedures_for_using_OCR TN.pdf).

HORIZONTAL AND VERTICAL DATUM IS TO THE GEODETIC REFERENCE POINT (GRP). THE ANTENNA IS A TOPCON TPSCR.G3 WITH SCIT RADOME (INSTALLED 06/08/2011). TRUE VERTICAL ANTENNA HEIGHT IS FROM THE GEODETIC REFERENCE POINT (GRP) TO THE BOTTOM OF THE ANTENNA PRE-AMP (BPA) AND IS 0.008 METERS (0.027 FEET).

