

GPS #: **PRADO-88-33**

Date Destroyed:

Date Revised: 4/15/2016

Benchmark Designation:

OCS Index Map:

Page/Grid:

City / Location: Prado Basin Area.

Scale Factor: 1.00000828

Ellipsoid Red. Factor: 0.99997616

Combination Factor: 0.99998444

Convergence Angle: -00 43 48.83

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35			0.000	0.000	
2007.00	33 55 50.89272	117 34 43.88283	2284891.40	6158572.80	500.58

References: 2015 Prado Basin GPS Survey.

Description:

FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK "PRADO-88-33", 105.0' SOUTH OF CENTERLINE OF FIFTH ST., 55.0' EAST FROM CENTERLINE OF CORYDON DR. SET ON TOP OF THE NE'LY CORNER OF A 11' X 4' CONCRETE CATCH BASIN.

NO
LOCATION
MAP